

QUANTITY	UNIT	ITEM	L & T CONST., INC.	C. WATTS & SONS CONST. CO., INC.	EUTAW CONST. CO., INC.	AVG. OF LOW BIDS
104.00	LF	6" PIPE UNDERDRAINS	42.01	12.00	35.52	29.84
635.00	CUYD	UNCLASS.EXCAV.FOR STRS-BR	22.05	22.50	20.54	21.70
459.90	CUYD	CLASS S CONCRETE - BRIDGE	645.06	660.00	600.82	635.29
313.50	CUYD	CLASS S(AE) CONCRETE - BRIDGE	656.09	670.00	611.09	645.73
952.00	LF	PRESTESS CONC GIRDERS (TY BT-72)	340.10	350.00	316.77	335.62
40.40	GAL	CLASS 1 PROTECT.SURF.TREATMENT	74.89	77.00	69.75	73.88
119,500.00	LB	REINF.STEEL-BRIDGE (GR 60)	0.81	1.00	0.75	0.85
870.00	LB	EPOXY COAT.REINF.STEEL-GR 60	1.76	1.80	1.64	1.73
1,683.00	LF	CONC.PILING (16" SQUARE)	81.10	83.00	75.57	79.89
73.00	LF	TEST PILE (16" SQUARE)	123.92	127.00	115.42	122.11
1,050.00	LF	PREBORING	43.07	44.00	40.12	42.40
3,640.00	LB	STR.ST.BM.SPANS (M270-GR50W)	13.97	14.25	13.01	13.74
6,432.00	CUIN	ELASTOMERIC BEARINGS	3.41	3.49	3.18	3.36
63.00	LF	ARM. JT W/NEOPRENE STRIP SEAL	141.51	145.00	131.80	139.44
1.00	EACH	BRIDGE NAME PLATE (TYPE D)	1,999.51	2,000.00	1,862.36	1,953.96
35.00	CUYD	CONCRETE RIPRAP	91.19	210.00	450.00	250.40
TOTAL AMOUNT BID FOR JOB			\$7,321,490.38	\$8,985,924.19	\$8,995,572.06	
TOTAL AMOUNT BID FOR BRIDGE			\$1,223,496.23	\$1,274,453.98	\$1,151,527.44	

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
07122	242.24	31.17	7,549.81	1A	NA
		A =	7,549.81		

1A 240' - CONT PRESTRESSED CONC GIRDER UNIT (120'-120') ON MULTI COL BENTS WITH CONC FOUNDATION PILES & CAST IN PLACE VERTICAL ABUTMENT W/CONCRETE FOUNDATION PILES.

1B NA

OUT TO OUT COST (\$/SF)=	\$1,223,496.23	/A =	\$162.06	* FHWA COST (\$/SF)=	\$1,220,304.58	/A =	\$161.64
LESS REMOVAL / TEMP. BR.	(\$/SF)	=	NA	EXISTING BR. REMOVAL (\$/SF)	=	NA	
NET COST (\$/SF)	=	\$162.06		* DEDUCT REMOVAL, TEMP. BR., RIPRAP, & FILTER BLANKET COSTS			

FUNCTION CLASS - FREEWAY & EXPRESSWAY  
 ON (02)

DESIGN SECTION - CJF